



GENERAL CONSTRUCTION NOTES:

1. SEE TTL DOCUMENT NO. 23-07-00986.00 FOR PAVEMENT DESIGN AND CONSTRUCTION RECOMMENDATIONS.
2. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE CODES, ORDINANCES, RULES, REGULATIONS, AND LAWS OF LOCAL, MUNICIPAL, STATE, OR FEDERAL AUTHORITIES HAVING JURISDICTION OVER THIS PROJECT. ALL PERMITS REQUIRED FOR CONSTRUCTION OPERATIONS SHALL BE OBTAINED BY THE CONTRACTOR.
3. THE GEORGIA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION OF ROADS AND BRIDGES, CURRENT EDITION, AND/OR SPECIAL PROVISIONS AND SUPPLEMENTAL SPECIFICATIONS SHALL GOVERN THE WORK ON THIS PROJECT.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING ALL UTILITY COMPANIES REGARDING LOCATION OF EXISTING UTILITIES AND SHALL BE RESPONSIBLE FOR THE COORDINATION OF WORK WHILE UTILITIES ARE BEING RELOCATED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR OF ANY DAMAGE TO UTILITIES RESULTING FROM WORK PERFORMED BY THE CONTRACTOR. THE EXISTING UTILITIES SHOWN ON THIS SET OF DRAWINGS REPRESENT APPROXIMATE LOCATIONS OF THE UTILITIES ACCORDING TO THE BEST INFORMATION AVAILABLE AND SHOULD BE USED FOR REFERENCE ONLY. THE CONTRACTOR SHALL TAKE THE NECESSARY STEPS TO MINIMIZE ANY INTERRUPTION OF UTILITY SERVICE TO THE SURROUNDING RESIDENTS.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INITIATING, SUPERVISING, AND MAINTAINING ALL SAFETY PROGRAMS THROUGHOUT THE DURATION OF CONSTRUCTION. ALL NECESSARY BARRICADES, SUFFICIENT LIGHTS, SIGNS, AND OTHER TRAFFIC CONTROL METHODS AS NECESSARY FOR THE PROTECTION AND SAFETY OF THE PUBLIC SHALL BE PROVIDED AND MAINTAINED BY THE CONTRACTOR THROUGHOUT THE DURATION OF CONSTRUCTION.
6. THE CONTRACTOR SHALL MAINTAIN, AT ALL TIMES, ADEQUATE AND SAFE ACCESS FOR ALL RESIDENTS AND/OR ADJOINING PROPERTY OWNERS DURING CONSTRUCTION.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING PROPER TRAFFIC CONTROL DEVICES AS REQUIRED BY THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
8. THE CONTRACTOR SHALL PROVIDE TRAFFIC CONTROL DURING CONSTRUCTION TO INSURE SAFE AND ORDERLY TRAFFIC FLOW IN THE PROJECT AREA.
9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY LAND OR PROPERTY BEYOND THE PROJECT CONSTRUCTION AREA WHICH MAY BE SUBJECT TO ANY EFFECTS OR BYPRODUCTS OF HIS CONSTRUCTION EFFORTS.
10. THE CONTRACTOR SHALL TAKE MEASURES TO PREVENT DAMAGE TO THE ADJOINING ROADS.
11. THE CONTRACTOR SHALL MAKE SPECIAL EFFORTS TO PREVENT SOIL EROSION AND SEDIMENTATION ON ADJACENT LANDS. THE CONTRACTOR SHALL PROVIDE TEMPORARY EROSION CONTROL MEASURES (SILT FENCE, HAY BALES, SWALES AND DITCHING, PONDING AND BASINS) AS NECESSARY TO CONTROL EROSION.
12. ALL DIMENSIONS SHOWN ON THESE DRAWINGS ARE TO EDGE OF PAVEMENT UNLESS OTHERWISE NOTED.
13. ALL ITEMS SHOWN TO BE REMOVED AND REPLACED SHALL BE REBUILT WITH SIMILAR MATERIALS AND SHALL MATCH EXISTING CONDITIONS WHERE POSSIBLE.
14. THE CONTRACTOR SHALL SAW CUT EXISTING ASPHALT AND CONCRETE PAVEMENT AS REQUIRED TO PRODUCE A SMOOTH JOINT WITH NEW PAVEMENT.
15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION STAKING.
16. THE CONTRACTOR SHALL KEEP RECORDS OF WORK PERFORMED ON A DAILY BASIS. THE CONTRACTOR SHALL PROVIDE ADEQUATE OVERSIGHT AND MANAGEMENT FOR HIS CONSTRUCTION EFFORTS.
17. COOPERATION AND COORDINATION BETWEEN ALL CONTRACTORS, UTILITY COMPANIES, AND SUB-CONTRACTORS ENGAGED IN THE WORK WITHIN AND ADJACENT TO THE CONSTRUCTION IS IMPORTANT FOR THE COMPLETION OF THIS PROJECT IN A TIMELY MANNER. IN THE CASE OF INTERFERENCE BETWEEN THE OPERATIONS OF THE DIFFERENT CONTRACTORS, UTILITY COMPANIES, AND SUB-CONTRACTORS, THE OWNER WILL BE THE SOLE JUDGE OF THE RIGHTS OF EACH AND THE SEQUENCE OF THE WORK NECESSARY TO EXPEDITE THE COMPLETION OF THIS PROJECT.
18. THE CONTRACTOR SHALL NOTIFY THE DIRECTOR OF ENGINEERING SERVICES AT LEAST 24 HOURS PRIOR TO THE START OF EACH PHASE OF CONSTRUCTION, SO THAT A COUNTY INSPECTOR CAN BE PRESENT.

DRAWN:	T. McENTYRE
CHECKED:	C. McLEOD
APPROVED:	C. McLEOD
DATE:	7/28/2023
SHEET:	1 of 2

**LOWNDES COUNTY FIRE RESCUE STATION 10
 PAVEMENT RESURFACING
 SITE PLAN**

